

CASE STUDY: BREEDON QUARRIES, BUXTON

PROJECT: Demolition of former quarry processing

plant

LOCATION: Ashwoodale Quarry, Buxton

CLIENT: Breedon Group

CONTRACT DURATION: 2 Months



Following a detailed site appraisal and proposal Euro Demolition and Dismantling Ltd were awarded the contract to carry out the demolition of redundant high level quarry processing equipment. The remaining buildings and equipment were to remain live as production of the quarry was to continue throughout the duration of the project.

Critical high level works were carried out at weekends with lesser works carried out during the weekdays, ensuring that quarry production remained unchanged.

Works included removal of high level truck rapid loaders, crusher buildings, conveyors, ducting, pipeworks through to switch gear buildings and primary product rapid loader hoppers.

All recovered steels were processed and recycled, including that of broke out hard standings and building foundations.

The client says "The lads adopted Breedon's standards very well. Very high standard of work performed by the Guys" – B Richardson, Quarry Manager